St. Ninian's Primary School, Stirling: Archaeological Evaluation Data Structure Report

AOC Project 23048 9th April 2015





St. Ninian's Primary School, Stirling:

Archaeological Evaluation Data Structure Report

On Behalf of: Robertson Construction Ltd.

Robertson House Castle Business Centre

Stirling FK9 4TZ

National Grid Reference (NGR): NS 7919 9185 (Centred)

AOC Project No: 23048

OASIS Entry: 208409

Prepared by: Jessica Lumb

Date of Fieldwork: 8th April 2015

Date of Report: 9th April 2015

This document has been prepared in accordance with AOC standard operating procedures.

Author: Jessica Lumb Date: 9th April 2015

Approved by: Martin Cook Date: 9th February 2015

Draft/Final Report Stage: Draft Date: 9th February 2015

Enquiries to: AOC Archaeology Group

Edgefield Industrial Estate

Edgefield Road Loanhead EH20 9SY

Tel. 0131 440 3593 Fax. 0131 440 3422

e-mail. admin@aocarchaeology.com



www.aocarchaeology.com

Contents

			Page				
Lis	t of Illu	ustrations	3				
Lis	t of Pla	ates	3				
Lis	List of Appendices						
Ab	stract		4				
1			5				
	1.1	Background	5				
	1.2	Site Location	5				
	1.3	Archaeological Background	5				
2	OBJECTIVE						
3	METHODOLOGY						
4	RESULTS						
5	CONCLUSION AND RECOMMENDATIONS						
6	REF	ERENCES	6				
		X 1: Trench Descriptions					
		X 2: Photographic Record					
ΑP	PENDI	X 3: 'Discovery and Excavation in Scotland' Report	13				

List of Illustrations

Figure 1 Evaluation trench location plan

List of Plates

Wall 1, Trench 2 Plate 1

Plate 2 Modern rubbish surrounding Wall 1, Trench 2

Plate 3 General view of Trench 1 Plate 4 General view of Trench 2

List of Appendices

Appendix 1 Trench Descriptions Appendix 2 Photographic Record

Appendix 3 'Discovery and Excavation in Scotland' Report

Abstract

This report presents the results of an archaeological evaluation undertaken in relation to a proposed development of a new school on the current site of St Ninian's Primary School, Stirling, to the immediate north of Torbrex Road and to the south of Stirling High School.

The evaluation required the excavation of two 20 m long trenches to identify the nature and extent of any archaeological remains within the development area, with the particular aim of establishing the presence or absence of a Roman Road.

No significant archaeological features or artefacts were located within the evaluation trenches.

The evaluation has clearly demonstrated that the Roman Road in the vicinity of the development area does not pass through the evaluation area.

No further works are considered necessary within the development area. This recommendation requires the approval of the Stirling Council Planning Officer (Archaeology).

1 INTRODUCTION

1.1 Background

1.1.1 AOC Archaeology Group have been commissioned by Stirling Council to undertake an archaeological evaluation at St Ninians Primary School prior to the erection of a new primary school within the existing school grounds. The extent of the required archaeological works has been determined by the Stirling Council.

1.2 Site Location

1.2.1 The development site lies within an urban setting to the immediate north of Torbrex Road and to the south of Stirling High School. To the east there are residential properties that face onto Berkeley Road. The development area is centred on NGR: NS 7919 9185.

1.3 Archaeological Background

- 2.1 The main archaeological site that is liable to be affected by this development is a possible Roman Road (HER id 1085.04). This Roman Road is aligned north to south and may pass through the eastern side of the development landtake.
- 2.2 The Stirling HER and the RCAHMS do not list any other known sites as lying within the development area however there are four historical findspots from the general locality of the development area that suggest the potential for the survival of hitherto unknown subsurface prehistoric remains. Firstly, there are prehistoric coarse stone tools in the form of a granite battle axe (NMRS No. NS79SE 37) and a ground stone axe (NMRS No. NS79SE 77). This is accompanied by a spearhead (NMRS No. NS79SE 36) and then lastly sherds from cinerary Urn (NMRS No. NS79SE 76) both of which probably date to the Late Bronze Age.

2 OBJECTIVE

2.1 The objective of the archaeological evaluation was to identify the nature and extent of any archaeological remains within the development area, with the particular aim of establishing the presence or absence of a Roman Road.

3 METHODOLOGY

- 3.1 The evaluation was initially proposed to excavate two 20 m long trenches in the development area. The footprint of the trenches were first cut through the tarmac with a floor cutter to limit the damage to the existing tarmac surface. The tarmac was deposited in a skip as per the clients' request.
- 3.2 All excavation was undertaken by a JCB 3CX excavator with 1.6 m wide ditching bucket. Excavation was undertaken in shallow units/spits until the first significant archaeological horizon. All machine excavation was supervised by an experienced field archaeologist and according to AOC Archaeology Group's standard operating procedures, and as per the methodology within the *Written Scheme of Investigation* (AOC 2015). The trenches were backfilled on completion of the evaluation.

4 RESULTS

- 4.1 The archaeological evaluation was undertaken on 8th April 2015. Weather conditions were good, allowing for good archaeological visibility throughout the evaluation. In total, 32 m of linear trench was opened aligned as per layout in Figure 1. Trench 2 was shortened to allow access to geotechnical surveyors currently working on the site and to avoid an unmarked electrical service (shown in Figure 1).
- 4.2 Trench 1 was oriented NE-SW and measured 20.0 m x 1.6 m wide x up to 0.64 m deep. It consisted of tarmac up to 0.1 m thick, overlying 'type 1' hardcore up to 0.2 m thick. The B-horizon consisted of compact dark brown/grey sandy silt with inclusions of modern ceramics and glass. A buried cable was encountered in Trench 1, 4.9 m from the SW end of the trench. This cable did not register on the Cable Avoidance Tool scan prior to excavation and is believed to be associated with the old transportable school buildings that used to be located in this area and as such, is disused.
- 4.3 Trench 2 was oriented NE-SW approximately 7.0 m SE of Trench 1 and measured 12.0 m x 1.6 m x up to 0.72 m deep. The B-horizon consisted of compact dark brown/black sandy silt with inclusions of modern ceramics, glass and rubbish including marbles, food wrappers and plastic bottles. A c.19th century rubbish pit was encountered 0.52 m from the SE end of Trench 2 and contained a possible bullet casing and a glass bottle. This pit measured 0.35 m in diameter x 0.33 m deep. Two walls were also encountered, Wall 1 (Plate 1) was located 3.0 m from the SE end and Wall 2 was located 2.6 m from the NW end. These walls were only one course thick and constructed of slabs measuring 0.32 m wide and roughly 0.5 m long and 0.1 m deep. It is likely they represent the foundations for the transportable buildings previously existing in this area.
- 4.4 No significant archaeological features or artefacts were located within the evaluation trenches. Close examination of the sections within the open trenches did not reveal any evidence for any type of road surface or remains of a Roman road.

5 CONCLUSION AND RECOMMENDATIONS

- 5.1 The evaluation has clearly demonstrated that the Roman Road in the vicinity of the development area does not pass through the evaluation area. The walls encountered in Trench 2 are likely to represent the foundations for the transportable buildings previously existing in this area. This is further demonstrated by the school rubbish located around these walls (Plate 2).
- 5.2 No further archaeological works are deemed necessary within this part of the development area. This recommendation will require the approval of the Planning Officer (Archaeology) for Stirling Council.

6 REFERENCES

AOC Archaeology 2015, St. Ninian's Primary School, Stirling: Archaeological Evaluation Written Scheme of Investigation Unpublished AOC project design

Scottish Government 2014 Scottish Planning Policy.

Scottish Government 2011 PAN 2/2011 Planning & Archaeology.



Plate 1 – Wall 1, Trench 2



Plate 2 – Modern rubbish surrounding Wall 1, Trench 2



Plate 3 - General view of Trench 1



Plate 4 - General view of Trench 2




Figure 1: Site plan showing proposed position of evaluation trenches

Acchaeology



St. Ninian's Primary School, Stirling: **Archaeological Evaluation Data Structure Report**

Section 2: Appendices

APPENDIX 1: Trench Descriptions

Trench 1

Dimensions 20 m by 1.6 m

Total Area 32 m² **Excavated Orientation** NE to SW

Soil Make-up Topsoil - Tarmac 0.1m thick

Made ground - Type 1 0.2m thick

B-horizon - Dark brown/grey sandy silt, compact with inclusions of modern ceramics and

glass 0.1-0.2m thick

Topsoil

Depth of Excavation 0.63 m None Significant Features

Other Features BT Cable, disused, 4.9m from SW end of trench

Natural Subsoil Mid brown/red sandy gravel with frequent inclusions of small to medium sub rounded stones

Finds 20th Century ceramics and glass within B-horizon (not retained)

Trench 2

Dimensions 12 m by 1.6 m Total Area 19.2 m² Excavated Orientation NE to SW

Soil Make-up Topsoil - Tarmac 0.07m thick

Made ground - Type 1 0.1m thick

B-horizon - Dark brown/grey sandy silt, compact with inclusions of modern ceramics and

glass 0.2-0.35m thick

Depth of Excavation 0.53m Significant Features None

Other Features Victorian rubbish pit – 0.52m from NE end of trench, 0.35m diameter x 0.33m deep

> Wall 1 - Orientated NW-SE, 3m from NE end of trench, 0.32m wide x width of trench Wall 2 – Orientated NW-SE, 2.6m from SW end of trench 0.32m wide x width of trench

Natural Subsoil Reddish brown sand and gravel.

Finds 20th Century ceramics, glass and rubbish within B-horizon (not retained)

Possible bullet casing and 20th Century glass within Victorian pit (not retained)


APPENDIX 2: Photographic Record

Digital Photographs

1-7 Contractor arrival onsite and general shots Various 8/4/15 8-12 CAT scanning area Various 8/4/15 13-16 Setting out trench Various 8/4/15 17-20 Setting up floor saw Various 8/4/15 21-37 Cutting out Trench 1 Various 8/4/15 38 Close up of floor saw blade - 8/4/15 39-40 Marking out Trench 2 Various 8/4/15 41-42 Removing tarmac from Trench 1 E 8/4/15 41-42 Removing tarmac from Trench 1 E 8/4/15 43 Cutting Trench 2 N 8/4/15 44 Tarmac removed, spoil heap S 8/4/15 45-53 Digging Trench 1 working shots Various 8/4/15 56 Possible post bole - 8/4/15 57-58 Cut cable in Trench 1 E 8/4/15 59 Trench 1 working shot NE 8/4/15 60-61 Cutting Trench 2 - 8/4/15	Frame	Description	From	Date
13-16 Setting out trench Various S/4/15	1-7	Contractor arrival onsite and general shots	Various	8/4/15
17-20 Setting up floor saw Various 8/4/15 21-37 Cutting out Trench 1 Various 8/4/15 38 Close up of floor saw blade - 8/4/15 39-40 Marking out Trench 2 Various 8/4/15 41-42 Removing tarmac from Trench 1 E 8/4/15 43 Cutting Trench 2 N 8/4/15 44 Tarmac removed, spoil heap S 8/4/15 45-53 Digging Trench 1 working shots Various 8/4/15 54-55 Working shots Trench 1 and 2 Various 8/4/15 56 Possible post hole - 8/4/15 57-58 Cut cable in Trench 1 E 8/4/15 59 Trench 1 working shot NE 8/4/15 60-61 Cutting Trench 2 - 8/4/15 62-63 SE facing section of Trench 1 SE 8/4/15 64 Possible post hole SE 8/4/15 65 Possible post hole SE 8/4/15 67 <td>8-12</td> <td>CAT scanning area</td> <td>Various</td> <td>8/4/15</td>	8-12	CAT scanning area	Various	8/4/15
21-37 Cutting out Trench 1 Various 8/4/15 38 Close up of floor saw blade - 8/4/15 39-40 Marking out Trench 2 Various 8/4/15 41-42 Removing tarmac from Trench 1 E 8/4/15 43 Cutting Trench 2 N 8/4/15 44 Tarmac removed, spoil heap S 8/4/15 45-53 Digging Trench 1 working shots Various 8/4/15 54-55 Working shots Trench 1 and 2 Various 8/4/15 56 Possible post hole - 8/4/15 57-58 Cut cable in Trench 1 E 8/4/15 59 Trench 1 working shot NE 8/4/15 60-61 Cutting Trench 2 - 8/4/15 60-61 Cutting Trench 2 - 8/4/15 62-63 SE facing section of Trench 1 SE 8/4/15 64 Possible post hole SE 8/4/15 65 Possible post hole SE 8/4/15 66	13-16	Setting out trench	Various	8/4/15
38 Close up of floor saw blade - 8/4/15	17-20	Setting up floor saw	Various	8/4/15
39-40 Marking out Trench 2 Various 8/4/15 41-42 Removing tarmac from Trench 1 E 8/4/15 43 Cutting Trench 2 N 8/4/15 44 Tarmac removed, spoil heap S 8/4/15 45-53 Digging Trench 1 working shots Various 8/4/15 54-55 Working shots Trench 1 and 2 Various 8/4/15 56 Possible post hole - 8/4/15 57-58 Cut cable in Trench 1 E 8/4/15 59 Trench 1 working shot NE 8/4/15 60-61 Cutting Trench 2 - 8/4/15 62-63 SE facing section of Trench 1 SE 8/4/15 64 Possible post hole SE 8/4/15 65 Possible post hole SE 8/4/15 66 Voided feature SE 8/4/15 67 End trench 1 NE 8/4/15 68-69 Tarmac dumping Various 8/4/15 70-72 Vehicle movement	21-37	Cutting out Trench 1	Various	8/4/15
41-42 Removing tarmac from Trench 1 43 Cutting Trench 2 A4 Tarmac removed, spoil heap 44 Tarmac removed, spoil heap 45-53 Digging Trench 1 working shots 46-55 Working shots Trench 1 and 2 56 Possible post hole 57-58 Cut cable in Trench 1 59 Trench 1 working shot 60-61 Cutting Trench 2 62-63 SE facing section of Trench 1 64 Possible post hole 55 Possible post hole 65 Possible post hole 66 Voided feature 67 End trench 1 68-69 Tarmac dumping 70-72 Vehicle movement 77-70 Digging Trench 2 78-74 Tarmac removal from area Various 84/15 77 Possible Wall 78-79 Digging Trench 2 81/4/15 82 Wall 1 83 Wall 1 84 Working shot Trench 2 85 Ri/4/15 86 Trench end 87 Backfilling Trench 2 88 Ri/4/15 89 Right 1 80 Right 1 80 Right 1 80 Right 1 81-41-5 81-41-5 82 Right 1 83 Right 1 84 Working shot Trench 2 85 Ri/4/15 86 Trench end 87 Backfilling Trench 1 88 Ri/4/15 89 Right 1 80 Right 1 80 Right 1 80 Right 1 80 Right 1 81 Right 1 82 Right 1 83 Right 1 84 Working shot Trench 2 85 Ri/4/15 86 Trench end 87 Backfilling Trench 1 88 Ri/4/15 89 Ri/4/15 80 Right 1 81 Right 1 82 Right 1 83 Right 1 84 Right 1 85 Right 1 86 Trench end 87 Backfilling Trench 1 86 Right 1 87 Backfilling Trench 1 88 Ri/4/15 89 Right 1 80 Right	38	Close up of floor saw blade	-	8/4/15
43 Cutting Trench 2 44 Tarmac removed, spoil heap 5 8/4/15 45-53 Digging Trench 1 working shots 54-55 Working shots Trench 1 and 2 56 Possible post hole 57-58 Cut cable in Trench 1 59 Trench 1 working shot 60-61 Cutting Trench 2 62-63 SE facing section of Trench 1 64 Possible post hole 55 Possible post hole 65 Possible post hole 66 Voided feature 67 End trench 1 68-69 Tarmac dumping 70-72 Vehicle movement 73-74 Tarmac removal from area 75-76 Digging Trench 2 70 Possible Wall 78-79 Digging Trench 2 80 Possible feature 81 Se Sid/15 82 Wall 1 83 Wall 1 84 Working shot Trench 2 86 Rid/15 87 Backfilling Trench 2 86 Rid/15 87 Backfilling Trench 2 88 Rid/15 89 Rid/15 80 Possible feature 80 Rid/15 81 Working shot cleaning Trench 2 81 Rid/15 82 Wall 1 84 Working shot Trench 2 85 Rid/15 86 Trench end 87 Backfilling Trench 1 8 Rid/15	39-40	Marking out Trench 2	Various	8/4/15
44 Tarmac removed, spoil heap S 8/4/15 45-53 Digging Trench 1 working shots Various 8/4/15 54-55 Working shots Trench 1 and 2 Various 8/4/15 56 Possible post hole - 8/4/15 57-58 Cut cable in Trench 1 E 8/4/15 59 Trench 1 working shot NE 8/4/15 60-61 Cutting Trench 2 - 8/4/15 62-63 SE facing section of Trench 1 SE 8/4/15 64 Possible post hole SE 8/4/15 65 Possible post hole SE 8/4/15 66 Voided feature SE 8/4/15 67 End trench 1 NE 8/4/15 68-69 Tarmac dumping Various 8/4/15 70-72 Vehicle movement Various 8/4/15 75-76 Digging Trench 2 Various 8/4/15 77 Possible Wall E 8/4/15 80 Possible feature <td< td=""><td>41-42</td><td>Removing tarmac from Trench 1</td><td>Е</td><td>8/4/15</td></td<>	41-42	Removing tarmac from Trench 1	Е	8/4/15
45-53 Digging Trench 1 working shots Various 8/4/15 54-55 Working shots Trench 1 and 2 Various 8/4/15 56 Possible post hole - 8/4/15 57-58 Cut cable in Trench 1 E 8/4/15 59 Trench 1 working shot NE 8/4/15 60-61 Cutting Trench 2 - 8/4/15 62-63 SE facing section of Trench 1 SE 8/4/15 64 Possible post hole SE 8/4/15 65 Possible post hole SE 8/4/15 66 Voided feature SE 8/4/15 67 End trench 1 NE 8/4/15 68-69 Tarmac dumping Various 8/4/15 70-72 Vehicle movement Various 8/4/15 73-74 Tarmac removal from area Various 8/4/15 77 Possible Wall E 8/4/15 80 Possible feature S 8/4/15 81 Working shot cleaning Trench 2	43	Cutting Trench 2	N	8/4/15
54-55 Working shots Trench 1 and 2 Various 8/4/15 56 Possible post hole - 8/4/15 57-58 Cut cable in Trench 1 E 8/4/15 59 Trench 1 working shot NE 8/4/15 60-61 Cutting Trench 2 - 8/4/15 62-63 SE facing section of Trench 1 SE 8/4/15 64 Possible post hole SE 8/4/15 65 Possible post hole SE 8/4/15 66 Voided feature SE 8/4/15 67 End trench 1 NE 8/4/15 68-69 Tarmac dumping Various 8/4/15 70-72 Vehicle movement Various 8/4/15 73-74 Tarmac removal from area Various 8/4/15 75-76 Digging Trench 2 Various 8/4/15 80 Possible Wall E 8/4/15 81 Working shot cleaning Trench 2 S 8/4/15 82 Wall 1 NE	44	Tarmac removed, spoil heap	S	8/4/15
56 Possible post hole - 8/4/15 57-58 Cut cable in Trench 1 E 8/4/15 59 Trench 1 working shot NE 8/4/15 60-61 Cutting Trench 2 - 8/4/15 62-63 SE facing section of Trench 1 SE 8/4/15 64 Possible post hole SE 8/4/15 65 Possible post hole SE 8/4/15 67 End trench 1 NE 8/4/15 67 End trench 1 NE 8/4/15 68-69 Tarmac dumping Various 8/4/15 70-72 Vehicle movement Various 8/4/15 73-74 Tarmac removal from area Various 8/4/15 75-76 Digging Trench 2 Various 8/4/15 78-79 Digging Trench 2 Various 8/4/15 80 Possible feature S 8/4/15 81 Working shot cleaning Trench 2 S 8/4/15 82 Wall 1 NE 8/	45-53	Digging Trench 1 working shots	Various	8/4/15
57-58 Cut cable in Trench 1 E 8/4/15 59 Trench 1 working shot NE 8/4/15 60-61 Cutting Trench 2 - 8/4/15 62-63 SE facing section of Trench 1 SE 8/4/15 64 Possible post hole SE 8/4/15 65 Possible post hole SE 8/4/15 66 Voided feature SE 8/4/15 67 End trench 1 NE 8/4/15 68-69 Tarmac dumping Various 8/4/15 70-72 Vehicle movement Various 8/4/15 73-74 Tarmac removal from area Various 8/4/15 75-76 Digging Trench 2 Various 8/4/15 78-79 Digging Trench 2 Various 8/4/15 80 Possible feature S 8/4/15 81 Working shot cleaning Trench 2 S 8/4/15 83 Wall 1 NE 8/4/15 84 Working shot Trench 2 NE	54-55	Working shots Trench 1 and 2	Various	8/4/15
59 Trench 1 working shot NE 8/4/15 60-61 Cutting Trench 2 - 8/4/15 62-63 SE facing section of Trench 1 SE 8/4/15 64 Possible post hole SE 8/4/15 65 Possible post hole SE 8/4/15 66 Voided feature SE 8/4/15 67 End trench 1 NE 8/4/15 68-69 Tarmac dumping Various 8/4/15 70-72 Vehicle movement Various 8/4/15 73-74 Tarmac removal from area Various 8/4/15 75-76 Digging Trench 2 Various 8/4/15 78-79 Digging Trench 2 Various 8/4/15 80 Possible feature S 8/4/15 81 Working shot cleaning Trench 2 S 8/4/15 82 Wall 1 NE 8/4/15 84 Working shot Trench 2 NE 8/4/15 85 Wall 2 NE 8/4/15	56	Possible post hole	-	8/4/15
60-61 Cutting Trench 2 - 8/4/15 62-63 SE facing section of Trench 1 SE 8/4/15 64 Possible post hole SE 8/4/15 65 Possible post hole SE 8/4/15 66 Voided feature SE 8/4/15 67 End trench 1 NE 8/4/15 68-69 Tarmac dumping Various 8/4/15 70-72 Vehicle movement Various 8/4/15 75-76 Digging Trench 2 Various 8/4/15 77 Possible Wall E 8/4/15 80 Possible feature S 8/4/15 81 Working shot cleaning Trench 2 S 8/4/15 82 Wall 1 SE 8/4/15 83 Wall 1 SE 8/4/15 84 Working shot Trench 2 NE 8/4/15 85 Wall 2 NE 8/4/15 86 Trench end SW 8/4/15 87 Backfilling Trench 1 E 8/4/15 88 Backfilling Trench 1 E 8/4/15 89 Backfilling Trench 1 E 8/4/15	57-58	Cut cable in Trench 1	Е	8/4/15
62-63 SE facing section of Trench 1 SE 8/4/15 64 Possible post hole SE 8/4/15 65 Possible post hole SE 8/4/15 66 Voided feature SE 8/4/15 67 End trench 1 NE 8/4/15 68-69 Tarmac dumping Various 8/4/15 70-72 Vehicle movement Various 8/4/15 73-74 Tarmac removal from area Various 8/4/15 75-76 Digging Trench 2 Various 8/4/15 77 Possible Wall E 8/4/15 80 Possible feature S 8/4/15 81 Working shot cleaning Trench 2 S 8/4/15 82 Wall 1 NE 8/4/15 83 Wall 1 SE 8/4/15 84 Working shot Trench 2 NE 8/4/15 85 Wall 2 NE 8/4/15 86 Trench end SW 8/4/15 87 <td>59</td> <td>Trench 1 working shot</td> <td>NE</td> <td>8/4/15</td>	59	Trench 1 working shot	NE	8/4/15
64 Possible post hole SE 8/4/15 65 Possible post hole SE 8/4/15 66 Voided feature SE 8/4/15 67 End trench 1 NE 8/4/15 68-69 Tarmac dumping Various 8/4/15 70-72 Vehicle movement Various 8/4/15 73-74 Tarmac removal from area Various 8/4/15 75-76 Digging Trench 2 Various 8/4/15 78-79 Digging Trench 2 Various 8/4/15 80 Possible feature S 8/4/15 81 Working shot cleaning Trench 2 S 8/4/15 82 Wall 1 NE 8/4/15 83 Wall 1 SE 8/4/15 84 Working shot Trench 2 NE 8/4/15 85 Wall 2 NE 8/4/15 86 Trench end SW 8/4/15 87 Backfilling Trench 1 E 8/4/15	60-61	Cutting Trench 2	-	8/4/15
65 Possible post hole SE 8/4/15 66 Voided feature SE 8/4/15 67 End trench 1 NE 8/4/15 68-69 Tarmac dumping Various 8/4/15 70-72 Vehicle movement Various 8/4/15 73-74 Tarmac removal from area Various 8/4/15 75-76 Digging Trench 2 Various 8/4/15 78-79 Digging Trench 2 Various 8/4/15 80 Possible feature S 8/4/15 81 Working shot cleaning Trench 2 S 8/4/15 82 Wall 1 NE 8/4/15 83 Wall 1 SE 8/4/15 84 Working shot Trench 2 NE 8/4/15 85 Wall 2 NE 8/4/15 86 Trench end SW 8/4/15 87 Backfilling Trench 1 E 8/4/15	62-63	SE facing section of Trench 1	SE	8/4/15
66 Voided feature SE 8/4/15 67 End trench 1 NE 8/4/15 68-69 Tarmac dumping Various 8/4/15 70-72 Vehicle movement Various 8/4/15 73-74 Tarmac removal from area Various 8/4/15 75-76 Digging Trench 2 Various 8/4/15 77 Possible Wall E 8/4/15 78-79 Digging Trench 2 Various 8/4/15 80 Possible feature S 8/4/15 81 Working shot cleaning Trench 2 S 8/4/15 82 Wall 1 NE 8/4/15 83 Wall 1 SE 8/4/15 84 Working shot Trench 2 NE 8/4/15 85 Wall 2 NE 8/4/15 86 Trench end SW 8/4/15 87 Backfilling Trench 1 E 8/4/15	64	Possible post hole	SE	8/4/15
67 End trench 1 NE 8/4/15 68-69 Tarmac dumping Various 8/4/15 70-72 Vehicle movement Various 8/4/15 73-74 Tarmac removal from area Various 8/4/15 75-76 Digging Trench 2 Various 8/4/15 77 Possible Wall E 8/4/15 78-79 Digging Trench 2 Various 8/4/15 80 Possible feature S 8/4/15 81 Working shot cleaning Trench 2 S 8/4/15 82 Wall 1 NE 8/4/15 83 Wall 1 SE 8/4/15 84 Working shot Trench 2 NE 8/4/15 85 Wall 2 NE 8/4/15 86 Trench end SW 8/4/15 87 Backfilling Trench 1	65	Possible post hole	SE	8/4/15
68-69 Tarmac dumping Various 8/4/15 70-72 Vehicle movement Various 8/4/15 73-74 Tarmac removal from area Various 8/4/15 75-76 Digging Trench 2 Various 8/4/15 77 Possible Wall E 8/4/15 78-79 Digging Trench 2 Various 8/4/15 80 Possible feature S 8/4/15 81 Working shot cleaning Trench 2 S 8/4/15 82 Wall 1 NE 8/4/15 83 Wall 1 SE 8/4/15 84 Working shot Trench 2 NE 8/4/15 85 Wall 2 NE 8/4/15 86 Trench end SW 8/4/15 87 Backfilling Trench 1 E 8/4/15	66	Voided feature	SE	8/4/15
70-72 Vehicle movement Various 8/4/15 73-74 Tarmac removal from area Various 8/4/15 75-76 Digging Trench 2 Various 8/4/15 77 Possible Wall E 8/4/15 78-79 Digging Trench 2 Various 8/4/15 80 Possible feature S 8/4/15 81 Working shot cleaning Trench 2 S 8/4/15 82 Wall 1 NE 8/4/15 83 Wall 1 SE 8/4/15 84 Working shot Trench 2 NE 8/4/15 85 Wall 2 NE 8/4/15 86 Trench end SW 8/4/15 87 Backfilling Trench 1 E 8/4/15	67	End trench 1	NE	8/4/15
73-74 Tarmac removal from area Various 8/4/15 75-76 Digging Trench 2 Various 8/4/15 77 Possible Wall E 8/4/15 78-79 Digging Trench 2 Various 8/4/15 80 Possible feature S 8/4/15 81 Working shot cleaning Trench 2 S 8/4/15 82 Wall 1 NE 8/4/15 83 Wall 1 SE 8/4/15 84 Working shot Trench 2 NE 8/4/15 85 Wall 2 NE 8/4/15 86 Trench end SW 8/4/15 87 Backfilling Trench 1 E 8/4/15	68-69	Tarmac dumping	Various	8/4/15
75-76 Digging Trench 2 Various 8/4/15 77 Possible Wall E 8/4/15 78-79 Digging Trench 2 Various 8/4/15 80 Possible feature S 8/4/15 81 Working shot cleaning Trench 2 S 8/4/15 82 Wall 1 NE 8/4/15 83 Wall 1 SE 8/4/15 84 Working shot Trench 2 NE 8/4/15 85 Wall 2 NE 8/4/15 86 Trench end SW 8/4/15 87 Backfilling Trench 1 E 8/4/15	70-72	Vehicle movement	Various	8/4/15
77 Possible Wall E 8/4/15 78-79 Digging Trench 2 Various 8/4/15 80 Possible feature S 8/4/15 81 Working shot cleaning Trench 2 S 8/4/15 82 Wall 1 NE 8/4/15 83 Wall 1 SE 8/4/15 84 Working shot Trench 2 NE 8/4/15 85 Wall 2 NE 8/4/15 86 Trench end SW 8/4/15 87 Backfilling Trench 1 E 8/4/15	73-74	Tarmac removal from area	Various	8/4/15
78-79 Digging Trench 2 Various 8/4/15 80 Possible feature S 8/4/15 81 Working shot cleaning Trench 2 S 8/4/15 82 Wall 1 NE 8/4/15 83 Wall 1 SE 8/4/15 84 Working shot Trench 2 NE 8/4/15 85 Wall 2 NE 8/4/15 86 Trench end SW 8/4/15 87 Backfilling Trench 1 E 8/4/15	75-76	Digging Trench 2	Various	8/4/15
80 Possible feature S 8/4/15 81 Working shot cleaning Trench 2 S 8/4/15 82 Wall 1 NE 8/4/15 83 Wall 1 SE 8/4/15 84 Working shot Trench 2 NE 8/4/15 85 Wall 2 NE 8/4/15 86 Trench end SW 8/4/15 87 Backfilling Trench 1 E 8/4/15	77	Possible Wall	Е	8/4/15
81 Working shot cleaning Trench 2 S 8/4/15 82 Wall 1 NE 8/4/15 83 Wall 1 SE 8/4/15 84 Working shot Trench 2 NE 8/4/15 85 Wall 2 NE 8/4/15 86 Trench end SW 8/4/15 87 Backfilling Trench 1 E 8/4/15	78-79	Digging Trench 2	Various	8/4/15
82 Wall 1 NE 8/4/15 83 Wall 1 SE 8/4/15 84 Working shot Trench 2 NE 8/4/15 85 Wall 2 NE 8/4/15 86 Trench end SW 8/4/15 87 Backfilling Trench 1 E 8/4/15	80	Possible feature	S	8/4/15
83 Wall 1 SE 8/4/15 84 Working shot Trench 2 NE 8/4/15 85 Wall 2 NE 8/4/15 86 Trench end SW 8/4/15 87 Backfilling Trench 1 E 8/4/15	81	Working shot cleaning Trench 2	S	8/4/15
84 Working shot Trench 2 NE 8/4/15 85 Wall 2 NE 8/4/15 86 Trench end SW 8/4/15 87 Backfilling Trench 1 E 8/4/15	82	Wall 1	NE	8/4/15
85 Wall 2 NE 8/4/15 86 Trench end SW 8/4/15 87 Backfilling Trench 1 E 8/4/15	83	Wall 1	SE	8/4/15
86 Trench end SW 8/4/15 87 Backfilling Trench 1 E 8/4/15	84	Working shot Trench 2	NE	8/4/15
87 Backfilling Trench 1 E 8/4/15	85	Wall 2	NE	8/4/15
or backming from the	86	Trench end	SW	8/4/15
88-89 End of day E 8/4/15	87	Backfilling Trench 1	Е	8/4/15
	88-89	End of day	E	8/4/15

APPENDIX 3: 'Discovery and Excavation in Scotland' Report

LOCAL AUTHORITY:	Stirling Council
PROJECT TITLE/SITE NAME	St. Ninian's Primary School, Stirling
PROJECT CODE:	AOC 23048
PARISH:	St. Ninians
NAME OF CONTRIBUTOR:	Jessica Lumb
NAME OF ORGANISATION:	AOC Archaeology Group
TYPE(S) OF PROJECT:	Archaeological Evaluation
NMRS NO(S)	NS88NW 4; NS88NW 10
SITE/MONUMENT TYPE(S):	N/A
SIGNIFICANT FINDS:	N/A
NGR (2 letters, 6 figures)	NS 83560 89271
START DATE (this season)	7 th April 2015
END DATE (this season)	7 th April 2015
PREVIOUS WORK (incl. DES	None
MAIN (NARRATIVE) DESCRIPTION: (May include information from other fields)	AOC undertook an archaeological evaluation in relation to a proposed development of a new school on the current site of St Ninian's Primary School, Stirling, to the immediate north of Torbrex Road and to the south of Stirling High School. The evaluation required the excavation of two 20 m long trenches to identify the nature and extent of any archaeological remains within the development area, with the particular aim of establishing the presence or absence of a Roman Road. No significant archaeological features or artefacts were located within the evaluation trenches. The evaluation has clearly demonstrated that the Roman Road in the vicinity of the development area does not pass through the evaluation area.
PROPOSED FUTURE WORK:	None
CAPTION(S) FOR ILLUSTRS:	
SPONSOR OR FUNDING BODY:	Robertson Construction Ltd
ADDRESS OF MAIN CONTRIBUTOR:	Edgefield Road Industrial Estate, Loanhead, Midlothian, EH20 9SY
EMAIL ADDRESS:	admin@aocarchaeology.com
ARCHIVE LOCATION (intended/deposited)	Archive to be deposited in NMRS





AOC Archaeology Group, Edgefield Industrial Estate, Edgefield Road, Loanhead EH20 9SY tel: 0131 440 3593 | fax: 0131 440 3422 | e-mail: admin@aocarchaeology.com